

PONDICHERRY UNIVERSITY  
ELECTRICAL WING

Schedule of Work

**Name of Work:** Providing dedicated earthing for research equipment and providing G.I sheet for junction box in lab. for Centre for Nanoscience & Technology in the Madanjeet School of Green Energy Technologies building.

Item No.	Description of Item	Qty.	Unit	Rate	Amount
1.	Providing and fixing 25mm x 6mm copper strip on surface or in recess for connections etc, as required.	15 mtr	mtr		
2.	Providing powder coated 3mm thick G.I sheet toward covering the junction boxes of network and electrical wiring in the floor of the laboratories. Colour: Ivory a) 12" x 8" - 6 nos. b) 20" x 7" - 3 nos. c) 20" x 11" - 2 nos. d) 15" x 12" - 1no. e) 24" x 12" 1 no. f) 27" x 10" - 1 no.	1.5 sq. mm	sq. mm.		
<b>Total</b>					

Terms & Conditions:

1. The work shall be carried out strictly in accordance with CPWD General Specifications for the Electrical works as amended up to date.
2. Prior approval of the Engineer in charge is required for all the materials to be used on works. Non- standard quality materials shall not be acceptable.
3. Bad workmanship shall not be accepted, Such work is liable for rejection and shall be rectified by the contractor at his own risk and cost.
4. Payment will be arranged after satisfactory completion of the work.
5. Amount will be arrived on the actual works done basis.
6. The work should be carried out immediately on receipts of this work order.
7. The rate for each item of work to be quoted in the enclosed schedule of work format only otherwise, the quotation in any other format is considered as invalid quotation.
8. The work should be completed within 15 days from the date of issue of the work order.

Name and signature of the Firm/  
Contractor with Seal.

  
 ASSISTANT ENGINEER(E)  
 18/5/17