

PONDICHERY UNIVERSITY
ENGINEERING WING

Er.N.SANKARAMOURTHY, B.E.,
EXECUTIVE ENGINEER

No.PU/EW/NIQ/2016-17/

Date: 07.12.2016

NOTICE INVITING QUOTATIONS

For and on behalf of Pondicherry University, Executive Engineer, Engineering wing, Pondicherry University invites sealed quotations from the eligible firms for the work of “Arresting the water seepage / leakage at Room no.50 through the walls, from first floor toilet, bathroom and drying clothes area in Madam Curie hostel building”. The rates should be filled in the schedule enclosed with this and placed in a sealed cover by superscribing the name of the work in the cover as mentioned above. An amount of Rs.1,000/- has to be furnished towards EMD which shall be in the form of demand draft from any one of the nationalized banks payable at Pondicherry, drawn in favour of the Finance officer, Pondicherry University. The notice with schedule can also be downloaded from the University web site www.pondiuni.edu.in and submitted

The filled in quotation shall to be placed in the tender box kept in the reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The quotations will be received up to 3.00 p.m. on 15.12.2016 and will be opened at 3.30 p.m. on the same day in the presence of tenderers those who present at the time of opening.

The Executive Engineer, Engineering wing, Pondicherry University reserves the right to accept or reject any or all quotation without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

PONDICHERY UNIVERSITY
ENGINEERING WING
SCHEDULE OF WORK

Name of the work: Arresting the water seepage / leakage at Room no.50 through the walls, from first floor toilet, bathroom and drying clothes area in Madam Curie hostel building

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1	Surface preparation: Cut open the cracks and construction joints, using necessary tools and clean the surface from loose, dirt & oil grease, bitumen particles for coating other works etc.,	32		Sqm	
2	Clean the surface from loose, dirt & oil particles. Supplying and applying of Epoxy base tile grout material in the tiles joint area, using with quick setting chemicals, & tape roll and other necessary things and tools etc, so as to completely seal the water leakage in the RCC slab, the cost including material and labour	24.80		Sqm	
3	Clean the surface, supplying and applying of quick setting chemicals and Polysulphide sealant in the floor trap area, so as to completely seal the water leakage to the RCC floor slab. The cost including material and labour	6		No.	
4	Making the 18mm holes in the wall and fixing the PVC pipe of 32mm dia in the outer wall of the first floor bathroom & corridor area, the cost including machine rental and labour	1		No.	
5	Clean the surface, Taking V groove or buttering were it was necessary, supplying and applying of Polysulphide (Size: 10mm x 15mm)	14		Rmt	
6	Clean the surface, supplying and applying two coats of polymer base modified slurry coating over the sealant and necessary area using with Dr.Fixit Pidicrete URP or its equalant	13.30		Sqm	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 20 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) VAT @ 3.5% will be deducted from the bill.

Contractor

Executive Engineer