

PONDICHERY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Internal painting and special repairs for newly established glass blowing box shop at Science Block-II .

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. 15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within	1.00		Each	
2 14.43	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete..	120.00		Sqm	
3 6.13.2	Half brick masonry with FPS bricks of class designation 35 in superstructure above plinth level upto floor V level in cement mortar 1:4 (1 cement: 4 coarse sand)	2.00		Sqm	
4 6.15	Extra for providing and placing in position 2 nos. 6mm dia MS bars at every third course of half brick masonry (with FPS bricks).	2.00		Sqm	
5 13.3.1	20mm cement plaster of mix 1:4 (1cement : 4 sqm fine sand)	4.00		Sqm	
6 13.43.1	Applying one coat of cement primer of approved brand and manufacture on wall surface - Cement primer	120.00		Sqm	
7 13.60.1 C	Wall painting with plastic emulsion paint Commercial of approved brand and manufacture to give an even shade - two or more coats on new work	165.00		Sqm	
8 9.21.2	Providing and fixing ISI marked flush door shutters conforming to IS:2202 (Part 1) non-decorative type, core of block board construction with frame of 1 st class hard wood and well matched teak 3 ply veneering with vertical	3.10		Sqm	

	grains or cross bands and face veneers on both faces of shutters. - 30 mm thick including ISI marked stainless steel butt hinges with necessary screws				
9 9.23	Extra for providing lipping with teak wood battens 25mm minimum depth on all edges of r area shutters (over all area of door shutter to be measured) over item no.9.20 and 9.21	3.10		Sqm	
10 13.50.1	Applying priming coat - with ready mixed pink or grey primer of approved brand and manufacture on wood work (hard and soft wood).	8.00		Sqm	
11 13.61.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade - Two or more coats on new work.	8.00		Sqm	
12 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade - One or more coats on old work.	10.00		Sqm	
13 9.100.1	Providing and fixing aluminium handles ISI marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc.complete :-125mm	2.00		Each	
14 9.97.2	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc.complete : -250x10mm	1.00		Each	
15 9.97.4	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc.complete : - 150x10mm	1.00		Each	

16 9.96.1	Providing and fixing aluminium sliding door bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with nuts and screws etc.complete:- 300x16mm	1.00		Each	
17 9.101.2	Providing and fixing aluminium hanging floor door stopper ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade with necessary screws etc.complete - Twin rubber stopper	1.00		Each	
18 MR	Providing and fixing white vitreous china laboratory sink with CI brackets CP brass chain with rubber plug 40mm CP brass waste and 40mm CP brass trap with necessary CP brass unions complete including painting of fittings and brackets cutting and making good the walls wherever required size 600x450x200mm	1.00		Each	
19 MR	Providing and fixing brass three way lab bib cock of approved quality. The rate including labours and materials etc., complete as direction by the Engineer – in-charge - 15 mm nominal bore.	1.00		Each	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within a period of 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.

Yours faithfully,

EXECUTIVE ENGINEER

CONTRACTOR