

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of work: Providing cement concrete pedestal to the steel tubular street light poles (6 nos) located between Cricket Stadium to C.V. Raman hostel

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. 2.31	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	14.00		Sqm	
2. 15.2.2	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead - 1:4:8 or leaner mix.	0.50		Cum	
3. 2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms , lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed	0.50		Cum	
4. 4.1.10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.- All work upto plinth level -1:5:10 (1 cement:5coarse sand : 10 graded stone aggregate 40mm nominal size)	0.15		Cum	
5. 4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.- All work upto plinth level -1:2:4 (1 cement:2coarse sand : 4 graded stone aggregate 20mm nominal size)	1.25		Cum	
6. 4.3.1	Centering shuttering including struttings,propping etc. and removal	9.00		Sqm	

	of form work for foundations, footings , bases for columns.- Using steel sheet with M.S.frames				
7. 13.1.1	12mm cement plaster of mix 1:4 (1cement : 4 sqm fine sand)	10.00		Sqm	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within a period of 10 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Executive Engineer