PONDICHERRY UNIVERSITY ENGINEERING WING

SCHEDULE OF WORK

Name of work: Provide a handrail at the steps opposite to the cooperative credit society in the Administrative block

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. 10.28	Providing and fixing AISI 316 grade stainless steel hand rail of 50mm (outer dia 2mm wall thickness) stainless steel pipe supported on 40x10mm stainless steel flat at 600mm centre to centre to a total height of 900mm from the finished floor level and fixing 4nos .of 25mm (outer dia and 2mm wall thickness) stainless steel pipe as guard rails through the S.S.flat , with a base plate of size 100x100x8mm, including fixing in the base plate in concrete / wall surfaces by 4 nos of M-8 anchor fasteners and polishing the entire stainless steel work to no.4 surface finish as per the direction of engineer - in - charge	12		metre	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 20 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer