

PONDICHERRY UNIVERSITY
ENGINEERING WING
SCHEDULE OF WORK

Name of the work: Replacing the existing damaged sanitary fittings and special repairs to the ground floor gents toilet at Department of Biotechnology

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. 18.5 4.3	Providing and fixing PTMT bib cock of approved quality and colour -15 mm nominal bore, 165 mm long, weighing not less than 110 gms	2.00		Each	
2. 18.5 6.1	Providing and fixing PTMT pillar cock of approved quality and colour - 15 mm nominal bore, 107 mm long, weighing not less than 110 gms	6.00		Each	
3. 18.6 3	Providing and fixing PTMT angle stop cock 15 mm nominal bore, weighing not less than 85 gms	11.00		Each	
4. 17.1 8.1	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete - 10 litre capacity - White	5.00		Each	
5. 17.2 8.1.1	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete -Semi rigid pipe 32mm dia	5.00		Each	
6. 13.8 8	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	60.00		Sqm	
7. 13.6 0.1	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade -two or more coats on new work /old work	60.00		Sqm	
8. 17.3 1	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete	6.00		Each	

9. 14.7 6	Cleaning and desilting of gully trap chamber, including removal of rubbish mixed with earth etc. and disposal of same, all as per the direction of Engineer-in-charge.	4.00		Each	
10. MR	Providing and fixing 45mm diameter and 60 cm long PVC drainage water spout pipe in the existing roof beam. The rate including demolishing cement concrete and re-plaster the surface smoothly with cement mortar 1:4 (1 cement: 4 fine sand) finished with a floating coat of neat cement complete as per the direction of the Engineer-in-charge.	1.00		Job	
11. MR	Acid cleaning for the existing Mosaic floors, glazed tiles work and removing the stains and decays to give a glassy look etc complete (The acid used shall be 32% concentrated hydrochloric acid after taking on the precautionary measures)	40.00		Sqm	
12. MR	Acid cleaning in the sanitary appliances like IWC,EWC, wash basin, Urinals and sink etc to give a glassy look etc complete as directed by the Engineer-in-charge.	43.00		Each	
	TOTAL				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 10 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer