

PONDICHERY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of work: Maintenance of UGC Academic Staff College

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 14.45.1	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade - Old work (one or more coats).	4350		sqm	
2 14.66.1	Finishing walls with Acrylic Smooth exterior paint of required shade - Old work (Two or more coats applied @ 1.67 lts/10 sqm.) on existing cement paint surface	5300		Sqm	
3 14.42.1	White washing with lime to give an even shade - Old work (two or more coats).	1800		Sqm	
4 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade - One or more coats on old work.	460		sqm	
5 14.43	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc., complete	120		sqm	
6 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50m lead	25		sqm	
7 13.3.1	20mm cement plaster of mix 1:4 (1 cement : 4 find sand)	25		sqm	
8 14.6.1	Renewing glass panes, with wooden fillets wherever necessary – Float glass panes of thickness 4mm	2		sqm	
	Total				

I hereby abide the rules and regulations stipulated in the CPWD form no. 6 & 8.

Contractor

Officer in-charge