

**PONDICHERRY UNIVERSITY**  
**ENGINEERING WING**

**SCHEDULE OF WORK**

**Name of the work:** Providing vitrified tiles flooring in the Library Hall at Community College Building, Lawspet

<b>S. No.</b>	<b>Description</b>	<b>Qty.</b>	<b>Rate Rs.P.</b>	<b>Unit</b>	<b>Amount Rs.P.</b>
1	Providing and laying vitrified floor tiles of size 60cm x 60cm (thickness to be specified by the manufacturer) with water absorption's less than 0.08% and confirming to IS 15622 of approved make (Nitco/Rak/Jhonson/Asian) in all colors and shades, laid on approved tile adhesive compound of 3mm thick including grouting the joints with white cement and matching pigments etc., complete size of tiles 600 x 600 mm	285.00		Sqm	
	<b>Total</b>				

I hereby abide the rules and regulations stipulated in the CPWD form no. 6 & 8.

**Contractor**

**Superintending Engineer**