

**PONDICHERRY UNIVERSITY**  
**ENGINEERING WING**  
**SCHEDULE OF WORK**

Name of the work: Replacing the damaged flooring tiles and fixing netlon mesh at Kalpana Chawla, Madam Curie, Ganga and Yamuna hostel buildings

<b>S. No.</b>	<b>Description</b>	<b>Qty.</b>	<b>Rate Rs.P.</b>	<b>Unit</b>	<b>Amount Rs.P.</b>
1. 15.2 3.1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	36		Sqm	
2. 11.3 7	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete.	36		sqm	
3. M.R	Supplying and fixing netlon mesh to the windows using with Velcro etc complete. The rate include cost of material and labour for stitching and fixing etc	45		Sqm	
	<b>TOTAL</b>				

**Terms & Conditions:**

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 20 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

**Contractor**

**Executive Engineer**