

ENGINEERING WING

SCHEDULE OF WORK

Name of work: Repair works at B-10 staff quarters building.

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. 15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead - of area 3 sqm and below	3		each	
2. 15.13.1	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead - of area 3 sqm and below	2		each	
3. 9.1.2p	Providing wood work in frames of doors , windows, clerestory windows and other frames , wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately) -Padak wood	0.15		cum	
4. A.R	Replastering and finishing the damaged cutting portion of the door wall wherever required including paint finishing etc.	1		Job	
5. 9.53	Providing 40 X 5 mm flat iron hold fast 40 cm long including fixing to frame with 10 mm diameter bots, nuts and wooden plugs and embeddings in cement concrete block 30 x10 x 15 cm 1:3:6 mix (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size)	10		each	
6. 9.100.1	Providing and fixing aluminium handles , ISI marked , anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade,with necessary screws etc, complete - 125 mm	5		each	
7. 9.97.3	Providing and fixing aluminium tower bolts , ISI marked , anodised (anodic coating not less than grade AC 10 as per IS :1868) , transparent or dyed to required colour or shade , with necessary screws etc. complete - 200 x10 mm	4		each	

8. 9.5.1.1p	Providing and fixing panelled or panelled and glazed shutters for doors, windows, and clerestory windows, including ISI marked M.S.pressed butt hinges bright finished of required size with necessary screws, excluding panelling which will be paid for separately , all complete - Padak wood – 35 mm thick shutters	1.50		sqm	
9. 14.6.2	Renewing glass panes,with wooden fillets wherever necessary - Float glass panes of thickness 5.5mm	1.50		sqm	
10. 9.7.1P	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors , windows and clerestory windows (area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick - Padak wood	2		sqm	
11. 9.21.2	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part 1) non - decorative type, core of block board construction with frame of 1 st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters - 30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	4		sqm	
12. 9.16.1.1P	Providing and fixing 25 mm thick shutters for cup board etc - panelled or panelled & glazed shutters - Padak wood including ISI marked anodised aluminium butt hinges with necessary screws.	2		sqm	
13. 9.114.2	Providing and fixing magnetic catcher of approved quality in cupboard / ward robe shutters , including fixing with necessary screws etc complete - Double strip horizontal type	2		each	
14. 9.23	Extra for providing lipping with teak wood battens 25 mm minimum depth on all edges of flush door shutters (over all area of door shutter to be measured)	4		sqm	
15. 13.50.1	Applying priming coat - with ready mixed pink or grey primer of approved brand and manufacture on wood work (hard and soft wood)	22		sqm	
16. 13.61.1	Painting with synthetic enamel paint of approved brand and manufacutre	22		sqm	

	to give an even shade - Two or more coats on new work				
17. 14.43	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scatches etc.complete	16		sqm	
18. 13.43.1	Applying one coat of water thinnable cement primer of approved brand and manufacturer on wall surface - water thinnable cement primer	16		sqm	
19. A.R	Wall painting with plastic emulsion paint- commercial of approved brand and manufacture to give an even shade- two or more coat on old work	141		Sqm	
20. 14.54.1	Wall painting with enamel paint - commercial of approved brand and manufacture to give an even shade- two or more coat on old work	5		sqm	
	Total				

Terms& Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within a period of 15 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer