

PONDICHERY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of work: Providing and fixing m.s. safety grills to the existing window opening at Mother Therasa mess annexure building

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 10.27	Supplying and fixing of steel grill work of m.s. angles, flats, squares and pipes including cost of welding charges, fixing in position in masonry walls with cement concrete 1:2:4 (1 cement : 2 course sand : 4 graded stone aggregate 12.5mm nominal size) including one coat of priming coat etc. complete.	2131		Kg	
2 13.61.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade - Two or more coats on new work	85.23		Sqm	
	Total				

I hereby abide by the rules & regulations stipulated in the CPWD form no.6 & 8

Contractor

Officer in-charge