

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of work: Providing and fixing steel gate at rear side of the Distance education examination building.

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. 10.5.1	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6 mm angle iron and 3 mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer. Using M.S. angels 40x40x6 mm for diagonal braces	4		sqm	
2. 13.6.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	8.50		Sqm	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 10 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer