

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Providing termite control and disinfestations services to Guest house-I building.

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 M.R	Providing termite control treatment with the following stage: i. Drilling at junction wall and floor. ii. Injecting the chemical in the drilled holes. iii. Plugging the drilled holes with matching colour. iv. Treatment the external wall of the building. v. Treating all the wood with wood preservative chemical. The rate include cost of all material and labour charges. (for 20 rooms (GF & FF), suites – 4 nos. (GF & FF).	963		Sqm	
2. M.R	Providing disinfestations service: This service will control cockroaches, ants and mosquitoes and the treatment will be in the form of liquid effective chemical spray which is odorless, stainless non toxic and eco-friendly. The rate include cost of all material and labour charges etc complete.				
	a) For suite rooms (Each room @ 56 Sqmt)	4 rooms		Each	
	b) For normal rooms (Each room @ 27 Sqmt)	20 rooms		Each	
	Total				

Terms & Conditions:

- 1)The rates specified are firm and not subject to any variation.
- 2)The work should be completed within 20 days.
- 3)Payment will be made only after completion of the entire work.
- 4)The material should be got approved before commencement of work.
- 5)The rate specified should be inclusive of GST.

CONTRACTOR

EXECUTIVE ENGINEER