

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Providing Open to Sky platform for two wheelers/ four wheelers parking in DDE building

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. 2.31	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	210.00		Sqm	
2. 2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms , lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed , within a lead of 50m -All kinds of soil.	4.00		Cum	
3. 2.27B	Supplying and filling with red earth (excluding rock) including cost and conveyance to the work site and stacking to the departmental gauge, spreading in layers not exceeding 20cm in depth, watering and consolidation using 0.5 tonne roller , or wooden or steel rammers etc.complete for making play fields, running tracks and court yards.	23.00		Cum	
4. 4.1.10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.- All work upto plinth level -1:5:10 (1 cement:5coarse sand : 10 graded stone aggregate 40mm nominal size)	27.00		Cum	
5. 4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.- All work upto plinth level -1:2:4 (1 cement:2coarse sand : 4 graded stone	16.00		Cum	

	aggregate 20mm nominal size)				
6. 11.13.1	Providing and fixing glass strips in joints of terrazo/ cement concrete floors. 40mm wide and 4mm thick.	150.00		Rmt	
7. 6.4.2	Brick work with FPS bricks of class designation 35 in superstructure above plinth level upto floor V level in all shapes and sizes in cement mortar 1:6 (1 cement : 6 coarse sand)	9.00		Cum	
8. 13.3.2	20mm cement plaster of mix cement mortar 1:6 (1 cement : 6 fine sand)	65.00		Sqm	
9. 13.46.1	Finishing walls with Acrylic Smooth exterior paint of required shade - New work (Two or more coat applied @ 1.67 ltr / 10 sqm over and including base coat of water proofing cement paint applied @ 2.20 kg / 10 sqm)	65.00		Sqm	
	Total				

I hereby abide the rules and regulations stipulated in the CPWD form no. 6 & 8.

Contractor

Executive Engineer