

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Replacing the damaged flooring tiles at room no.FF-15 of girls hostel (administrative block) in Pondicherry University, Karaikal campus

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 15.2 3.1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50m lead - For thickness of tiles above 10mm and upto 25mm.	47.00		sqm	
2 11.4 1.2A	Providing and laying fully vitrified floor tiles of size 60x60cm (thickness to be specified by the manufacturer) with water absorption's less than 0.08% and conforming to IS: 15622 of approved make (Nitco / Rak / Johnson / Asian) in all colors and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600mm.	47.00		sqm	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 20 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer