

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of work: Arresting leakages to the Auditorium of the Library annex building

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. MR	Providing and laying high performance self adhesive butyl flashing strip (Durastrip- B brand) at the bolt holes, corners, junctions and wherever gaps found over the CCGL roofing and areesting the invisible pin holes at the bolted points by applying silicon adhesive gel of “ Asian Make” so as to arrest the of CCGL roofing. The rate includes the cost of matrails labout charges and all taxes and levies	50		Sqm	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 15 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer