

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of work: Providing and fixing safety grill gate in front of PUTA office and Faculty club					
Sl.No	Description	Qty	Rate	Unit	Amount
1	Code No: 10.27				
	Supplying and fixing of steel grill work of m.s. angles, flats, squares and pipes including cost of welding charges, fixing in position in masonry walls with cement concrete 1:2:4 (1 cement : 2 course sand : 4 graded stone aggregate 12.5mm nominal size) including one coat of priming coat etc. complete.	175.00		Kg	
2	Code No: 13.60.1A				
	Wall painting with plastic emulsion paint Royal of approved brand and manufacture to give an even shade - two or more coats on new work	1.00		Sqm	
3	Code No: MR				
	Supplying and fixing of G.I. Sheet (1.5mm thick) fixed with over the gate. The rate including cutting, hoisting, fixing in position and applying coat of approved steel primer all complete as per the direction of Engineer in charge	1.00		Job	
4	Code No: 13.61.1				
	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade - Two or more coats on new work.	6.00		Sqm	
				Total	

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 20 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.

Contractor

Executive Engineer

