

**PONDICHERY UNIVERSITY**  
**ENGINEERING WING**

**SCHEDULE OF WORK**

*Name of the work:* Painting the compound wall at Vice Chancellor official residence

<b>S. No.</b>	<b>Description</b>	<b>Qty.</b>	<b>Rate Rs.P.</b>	<b>Unit</b>	<b>Amount Rs.P.</b>
1 14.1.1	Repairs to plaster of thickness 12mm to 20mm in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete including disposal of rubbish to the dumping ground within 50 metres lead - With cement mortar 1:4 (1 cement : 4 fine sand).	10.00		sqm	
2. M.R	Cleaning the bushes and removing the unwanted plants over the compound wall inner and outer area including disposal etc.,. The rate to be quoted for supply of labour only.	25.00		Nos.	
3. 13.43.1	Applying one coat of cement primer of approved brand and manufacture on wall surface - Cement primer	800.00		sqm	
4 14.43	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	800.00		sqm	
5 AR	Wall painting with Apex weather proof exterior emulsion paint of the approved brand and manufacture to give an even shade-two or more coats on old work	2900.00		sqm	
6 13.52.1	Finishing with epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer specifications including appropriate priming coat, preparation of surface, etc. complete – On Steel work.	300.00		sqm	
7 M.R	Painting with gold paint of approved brand (MRF-metallic gold paint) and manufacture to give an even shade one or more coats on old steel work for Sharp edge design grill etc.	794.00		Nos.	
	<b>Total</b>				

**Contractor**

**Executive Engineer**