

**PONDICHERRY UNIVERSITY**  
**ENGINEERING WING**

**SCHEDULE OF WORK**

Name of work: Painting the fungal infected food science lab with Anti-Fungal paint.  
Pondicherry University

| <b>S. No.</b>  | <b>Description</b>   | <b>Qty.</b> | <b>Rate Rs.P.</b> | <b>Unit</b> | <b>Amount Rs.P.</b> |
|----------------|--|-------------|-------------------|-------------|---------------------|
| 1<br>13.91     | Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete  | 80.00       |                   | Sqm         |                     |
| 2<br>13.98.1   | Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: One or more coats on old work sqm   | 55.00       |                   | Sqm         |                     |
| 3.<br>13.48A.1 | Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm. sqm 146.20 | 80.00       |                   | Sqm         |                     |
| 4<br>13.99.1   | Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work  | 12.00       |                   | Sqm         |                     |
| 5<br>13.46.1   | Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 Sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm  | 130.00      |                   | Sqm         |                     |
| 6<br>22.14.2   | Grading roof for water proofing treatment Cement mortar 1:3 (1 cement : 3 coarse sand)   | 1.00        |                   | Cum         |                     |
|                | <b>Total</b>   |             |                   |             |                     |

**Terms & Conditions:**

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 20 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

**Contractor**

**Executive Engineer**