

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Providing and fixing of gypsum board false ceiling at Gym building for Gents & Ladies

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1	Providing and fixing false ceiling works using superior fire rated gypsum board of 12.5mm tk mounted on GI frame work with ceiling section of size 80x26x0.55x3660 mm spacing at 600mm c/c suspended from ceiling using hanger rods at 1200mm c/c with screw to level and line and applying one coat of primer , two coats of putty followed by and reflective paint in front of the stage area to the required shape and size , including scaffolding etc. complete as directed by the engineer -in-charge upto 6.5m height	500		Sqm	
	Total				

I hereby abide the rules and regulations stipulated in the CPWD form no. 6 & 8.

Contractor

Superintending Engineer