

PONDICHERRY UNIVERSITY
ENGINEERING WING
SCHEDULE OF WORK

Name of work: Replacement of worned main gate 2 (OUT)

Sl. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 10.27	Supplying and fixing of steel grill work of m.s. angles, flats, squares and pipes including cost of welding charges, fixing in position in masonry walls with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 12.5mm nominal size) including one coat of priming coat etc. complete	850.00		kg	
2 13.52.1	Finishing with epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface , etc. complete - on steel work	200.00		139.76	
3 15.18	Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismembering and stacking within 50 metre lead.	850.00		Kg	
4 MR (DED)	Sale of dismantled steel gate At in main gate No II ,the amount will be recovered from the bill on actual weight basics (deduct)	850.00		Kg	
5 11.7	Cement concrete pavement with 1:2:4 (1 cement : 2 coarse sand: 4 graded stone aggregate 20 mm nominal size) including finishing complete	6.00		Cum	

6 14.67.1	Finishing walls with premium acrylic smooth exterior paint with silicon additives of required shade - old work (two or more coats applied @ 1.43 ltr / 10 sqm) over existing cement paint surfac	30.00		sqm	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 20 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer