

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of work: Painting the fungal infected food science lab with Anti-Fungal paint.
Pondicherry University

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 13.91	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	80.00		Sqm	
2 13.98.1	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: One or more coats on old work sqm	55.00		Sqm	
3. 13.48A.1	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm. sqm 146.20	80.00		Sqm	
4 13.99.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	12.00		Sqm	
5 13.46.1	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 Sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm	130.00		Sqm	
6 22.14.2	Grading roof for water proofing treatment Cement mortar 1:3 (1 cement : 3 coarse sand)	1.00		Cum	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 20 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer