

**PONDICHERRY UNIVERSITY
ENGINEERING WING**

Name of Work: Special maintenance to the Earth science building

SCHEDULE OF WORK

| S.No | Description | Qty | Rate | Unit | Amount |
|-------------|--|------------|-------------|-------------|---------------|
| 1 | Code no:14.43 | | | | |
| | Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. | 325.00 | | sqm | |
| 2 | Code no:14.66.1 | | | | |
| | Finishing walls with Acrylic Smooth exterior paint of required shade - Old work (Two or more coats applied @ 1.67 lts/10 sqm.) on existing cement paint surface | 325.00 | | sqm | |
| 3 | Code no:5.3 | | | | |
| | Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15 degree landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto floor five level excluding the cost of centering, shuttering,finishing and reinforcement with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size). | 16.75 | | cum | |
| 4 | Code no:MR | | | | |
| | supplying and laying of bitumen sheet of 1mm thick over the expansion joint and the tail ends covered with bitumen adhesive . The rate includes the cost of materials, labours etc., complete.as per the direction by the Engineer-in-chare | 255.00 | | Sqm | |
| 5 | Code no:2.27 | | | | |
| | Supplying and filling in plinth with sand under floors including, watering, ramming consolidating and dressing complete. | 1.00 | | cum | |
| 6 | Code no:4.1.10 | | | | |
| | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.- All work upto plinth level -1:5:10 (1 cement:5coarse sand : 10 graded stone aggregate 40mm nominal size) | 0.75 | | cum | |

| | | | | | |
|-----------|---|------|--|------------|--|
| 7 | Code no:4.1.3 | | | | |
| | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.- All work upto plinth level -1:2:4 (1 cement:2coarse sand : 4 graded stone aggregate 20mm nominal size) | 0.75 | | cum | |
| 8 | Code no:MR | | | | |
| | To make good the fallen granite floor skirting in original position by using cement slurry or suitable adhesive etc., as directed by Engineer-in-charge | 7.00 | | Rm | |
| 9 | Code no:MR | | | | |
| | Providing and fixing brass three way lab tap of approved quality - 15mm nominal bore. | 2.00 | | No | |
| 10 | Code no:21.3.3 | | | | |
| | Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc., with PVC / neoprene gasket etc., complete as per the architectural drawings. (cost of aluminium snap beading shall be paid in basic item) : With float glass panes of 6.0mm thickness. | 1.20 | | Sqm | |
| | | | | Total | |
| | | | | Say | |

I hereby abide by the rules & regulations stipulated in the CPWD form no.6 & 8

Contractor

Assistant Engineer