

**PONDICHERRY UNIVERSITY**  
**ENGINEERING WING**

**SCHEDULE OF WORK**

*Name of the work:* Providing mosquito proof net for the windows at all the Gents hostel

<b>S.No.</b>	<b>Description</b>	<b>Qty.</b>	<b>Rate Rs.P.</b>	<b>Unit</b>	<b>Amount Rs.P.</b>
1 MR	Supplying and fixing fly proof netlon mesh of approved quality on the existing wooden / steel / aluminium window opening using Velcro. The rate includes cost of all material including stitching charge of Velcro fixing in position using staplers transport charges and labour charges etc.,	1000		Sqm	
2 9.40.2. 2P	Providing and fixing wooden moulded beading to door and window frames with iron screws , plugs and priming coat on unexposed surface etc. complete: Padak wood 50X20mm	1900		M	
3 13.61. 1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade - Two or more coats on new work.	190		Sqm	
	<b>Total</b>				

I hereby abide the rules and regulations stipulated in the CPWD form no. 6 & 8.

**Contractor**

**Executive Engineer**