PONDICHERRY UNIVERSITY ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Providing and laying floor and wall tiles at Animal house

S.No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 11.41. 2A	Providing and laying fully vitrified floor tiles of size 60x60cm (thickness to be specified by the manufacturer) with water absorption's less than 0.08% and conforming to IS: 15622 of approved make (Nitco / Rak / Johnson / Asian) in all colors and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600mm.	157		Sqm	
2 11.36 C	Providing and fixing 1st quallity ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacture of approved make (Jhonson / Asian / Somany / Nitco) in all colours, shades of size 300 x 600 mm in skirting, risers of steps and dados over 12mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm. Including pointing in white cement mixed with pigment of matching shade complete size 300x600mm	206		Sqm	
3 14.17	Raking out joints in lime or cement mortar and preparing the surface for re-pointing or replastering including disposal of rubbish to the dumping ground within 50 metres lead.	206		Sqm	
	Total				

I hereby abide by the rules & regulations stipulated in the CPWD form no.6 & 8 $\,$

Contractor

Executive Engineer