

**PONDICHERY UNIVERSITY**  
**ENGINEERING WING**

**SCHEDULE OF WORK**

Name of the work: Replacing the existing damaged door frame at Centre for Bioinformatics.

<b>S. No.</b>	<b>Description</b>	<b>Qty.</b>	<b>Rate Rs.P.</b>	<b>Unit</b>	<b>Amount Rs.P.</b>
1.	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 m lead - Of area 3 sq. metres and below.	1.00		Each	
2.	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 m lead - Of area beyond 3 sq. metre.	1.00		Each	
3.	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position - Padak wood	0.11		Cum	
4.	Providing 40x5 mm flat iron hold fast 40cm long including fixing to frame with 10mm diameter bolts, nuts and wooden plugs and embedding in cement concrete block 30x10x15cm 1:3:6 mix (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size)	12.00		Each	
5.	Dismantling tile work in floors and roofs, dados laid in cement mortar including stacking material within 50m lead - For thickness of tiles above 10mm and upto 25mm.	3.00		Sqm	
6.	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : 15622 (thickness to be specified by the manufacture of approved make (Jhonson / Asian / Somany / Nitco) in all colours,	3.00		Sqm	

	shades of size 300 x 450 mm as approved in skirting, risers of steps and dados over 12mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm. Including pointing in white cement mixed with pigment of matching shade complete. - size 300x450mm				
7.	Providing and fixing PVC corner beading of required size to suit the thickness of the wall tile at the corner joints of dado works	3.00		Rmt	
8.	Applying priming coat - with ready mixed Puducherry Region pink or grey primer of approved brand and manufacture on wood work (hard and soft wood).	18.00		Sqm	
9.	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade - Two or more coats on new work.	18.00		Sqm	
	<b>Total</b>				

**Terms & Conditions:**

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 20 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.

**Contractor**

**Executive Engineer**