

PONDICHERY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Maintenance of Auditorium at School of Management Building.

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 15.39.3	Dismantling wooden boardings in lining of walls and partitions, excluding supporting members but including stacking within 50m lead - Thickness above 25mm upto 40mm	40.00		sqm	
2 14.46	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	252.00		sqm	
3 14.54 .1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade - One or more coats on old work.	30.00		sqm	
4 13.60.1 B	Wall painting with plastic emulsion paint - Premium of approved brand and manufacture to give an even shade - two or more coats on new work	390.00		sqm	
5 11.53.3	Providing and fixing homogeneous Polyvinyl chloride sheet in flooring and skirting in approved pattern on a smooth and damp proof base using rubber based adhesives of approved quality including rolling with light wooden roller weighing about 5kg. All complete - 2mm thick – sheet	165.00		sqm	

6 MR	Providing and fixing 3mm woolen carpet flooring and skirting in approved pattern on a smooth and damp proof base using rubber based adhesives of approved quality including rolling with light wooden roller weighing about 5kg. All complete – as per the direction of Engineer in-charge for dias	30.00		sqm	
7 9.35.2	Providing and fixing in wall lining flat pressed three layer (medium density)particle board or graded wood prelaminate one side decorative lamination on other side balancing lamination grade 1,type II , IS: 12823 marked including priming coat on unexposed surface , with necessary fixing arrangement and screws etc. complete : - 18mm thick	40.00		sqm	
8 MR	Dismantling and re fixing the audience chair in position after laying the vinyl flooring in the floor area	100.00		Each	
9 MR	Dismantling and re fixing the Pondicherry university logo and letters in the Dias back drop wall	1 job		Job	
10 MR	Supplying and fixing Fleet screen using approved quality screen cloth with not less than 1200 mm with necessary curtain rod rainbow , screen cloth should be not less than 140.00 for screen cloth . the rate includes of all labour charge for material, transport , and fixing charges etc., complete as per the direction of engineer in charge				
	a) For handloom materials	35.00		Mt	
	b) Inner material	35.00		Mt	

	c) Stitching charge `	12.00		Each	
	d) Curtain rod	12.00		Mt	
	e) Rod fixing charge	4.00		Each	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 20days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.

EXECUTIVE ENGINEER