

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of work: Internal and external painting, special repairs to the computer science department class room at science block-II

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50m lead.	10.00		Sqm	
2. 14.43	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	31.00		Sqm	
3. 13.43.1	Applying one coat of cement primer of approved brand and manufacture on wall surface - Cement primer	31.00		Sqm	
4. 13.26A	Providing and applying ready mixed wall putty (JK / BIRLA) of 2mm thickness over plastered surface to prepare the surface even and smooth complete	31.00		Sqm	
5. MR	Wall painting with plastic emulsion commercial of approved brand and manufacture to give an even shade two or more coats on old work	80.00		Sqm	
6. 14.72	Providing and fixing double scaffolding system (cup lock type) on the exterior side, upto seven story height made with 40mm dia M.S. tube 1.5m centre to centre horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it is a serviceable condition for the required duration as approved and removing it there after. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc. wherever required for inspection of work at required locations with	80.00		Sqm	

	essential safety features for the workmen etc. complete as approved. The elevational area of the scaffolding shall be measured for payment purpose. The payment will be made once irrespective of duration of scaffolding. (To be used for maintenance work judicially necessary)				
7. 13.3.1	20mm cement plaster of mix 1:4 (1cement : 4 sqm fine sand)	10.00		Sqm	
8. 13.46.1	Finishing walls with Acrylic Smooth exterior paint of required shade - New work (Two or more coat applied @ 1.67 ltr / 10 sqm over and including base coat of water proofing cement paint applied @ 2.20 kg / 10 sqm)	10.00		Sqm	
	Total				

Terms& Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within a period of 10 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer