PONDICHERRY UNIVERSITY ELECTRICAL WING

Schedule of Work

<u>Name of Work</u>: Supplying, installing, testing and commissioning of package air conditioning plants for Ultra Clean Laboratory to the newly constructed Earth Science Department at Pondicherry University Campus.

S.	Description of Thom	~ +.	1 15:4	Data	A see a const
No.	Description of Item Supplying, installation, testing	Qty	Unit	Rate	Amount
1.	and commissioning of floor				
	mounted made with CRCA/GI				
	sheet powder coated panels of 11				
	ton capacity, twin circuit package				
	air conditioner comprising of the				
	following:				
	a) Scroll type hermetically				
	sealed compressors suitable for				
	operation with R-22 refrigerant				
	on 380-420 volts, 3 phase, 50Hz				
	Alternate supply with internal				
	over load protection.				
	b) Air-cooled condenser				
	powder coated with inner grooved				
	copper tubes, hydraulically				
	bonded to corrugated, slit	1	Cash		
	aluminium anti corrosion coated blue fins, propeller type fan and	1	Each		
	suitable motor, necessary release				
	valve, base supports, rubber pads				
	and base for outdoor use.				
	c) Indoor unit (evaporator)				
	with inner grooved copper tube,				
	hydraulically bonded to				
	corrugated, slit aluminium fins,				
	statically & dynamically balanced				
	centrifugal fans, suitable motor,				
	and thermostatic expansion valve.				
	d) Filter & drier, air filters,				
	LP, HP pressure cut outs,				
	thermostat				
	e) Control panel fixed indoor				
	unit with micro processor based				
	control with temperature control,				
	compressor ON/OFF, starters for main compressor motor,				
	condenser motor, contactors,				
	time delay, single phasing				

	preventor, phase reversal protections, digital display for voltage, current, temperature cut off, self diagnosis function for faults, partial load operation with memory back up, auto restart after power failure, programmable timer with necessary cabling. f) Supply and charging the required quantity of refrigerant 22 and compressor oil, leak testing, vaccumising the entire system as required. Make:BlueStar/Carrier/LG/ETA/Voltas			
2.	Hard drawn copper piping of suitable size connecting refrigerant circuits both suction & discharge sides, control cable, earthing etc., between indoor and out door unit(Both suction and discharge line will be taken as single unit for measurement purpose).	50	mtr	
3.	Supplying, installation of MS Callar damper with canvass cover to connect the AC plant outlet and duct/plenum as required.	1	Each	
4.	Supply and installation of GI ducting of 20 G with suitable acoustical insulation for plenum with provision for micro filter compartment including anchor fasteners and supporting angles as required.	12	Sq.mt	
5.	Supply and installation of GI ducting of 22 G for supply and return air including anchor fasteners and supporting angles as required.	30	Sq.mt	
6.	Supplying, installation of powder coated coated Aluminium Grill with sufficient louvers to be fixed on GI ducting for air distribution.	6	Each	

7.	Room air dilution modules with HEPA filters made of 100% micro fibre glass to filter 0.3μ and large particles at 99.97% minimum efficiency, to be installed in existing wall/surface of clean room(Total capacity 1200 cfm).	6	Each		
8.	Fire dampers with control from the fire alarm system.	3	Each		
9.	Thermostic temperature control & dehumidication with electrical strip heaters.	1	1 Lot		
10.	Temperature indicator and pressure indicator.	1	1 set		
11.	Fresh air dampers with filters and bird screen.	1	Each		
12.	Minor civil works for mounting outdoor units and drawing copper pipe on wall including mounting steel angles to fix outdoor unit wherever necessary as per site condition.	2	Each		