

PONDICHERY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

**Name of the work: Providing and Fixing Steel Grill in the G.F Room Windows at
UMISARC Building**

Sl.No	Description	Qty	Unit	Quoted Rate (Rs.p)	Amount (RS.p)
1 10.27	Supplying and fixing of steel grill work of m.s. angles, flats, squares and pipes including cost of welding charges, fixing in position in masonry walls with cement concrete 1:2:4 (1 cement : 2 course sand : 4 graded stone aggregate 12.5mm nominal size) including one coat of priming coat etc. complete.	2500.00	Kg		
2 13.61.1	Painting with synthetic enamel paint of approved brand and manufacture to give aneven shade - Two or more coats on new work.	100.00	Sqm		
3 13.48.1	Finishing walls with Deluxe Multi surfacepaint system for interiors and exteriors using primer as per manufacturers specifications - Two or more coats applied @ 1.25 ltr / 10 sqm over and including one coat of special primer applied @ 0.75 ltr /10 sqm.	25.00	Sqm		
				Total	

Terms & Conditions:

- i) The rates specified are firm/contractor and not subject to any variation.
- ii) The work should be completed within a period of 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The materials to be used in the work shall be got approved by the Engineer-in - Charge before commencement of work.
- v) The rate quoted shall including all taxes and levies.
- vi) Necessary I.T and VAT will be deducted from the bill.

Contractor

Executive Engineer