PONDICHERRY UNIVERSITY
ENGINEERING WING
SCHEDULE OF WORK

NAME OF WORK: Providing Aluminum Partition at first floor of the school of social science Seminar Hall For The Purpose Of CLIL and Women's Cell

SI No:	Description	Qty	Rate	Unit	Amount
1 21. 1.1. 1	Providing and fixing aluminimum work for doors, windows, ventilators and partitions with extruded built up standard tubular sections / appropriate Z sections and other sections of approved make conforming to IS : 733 and IS : 1285, fixed with rawl plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC / neoprene felt etc. Aluminimum sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminimum snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings. (Glazing and panelling to be paid for separately) : For fixed portion. Anodised aluminimum (anodised transparent or dyed to required shade according to IS : 1868, Minimum anodic coating of grade AC 15)	90.00		Kg	
2 21. 2.2	Providing and fixing 9mm thick prelaminated particle board flat pressed three layer or\ graded wood particle board conforming to IS : 12823 grade 1 type II in panneling fixed in aluminimum doors, windows, shutters and partition frames with C.P. brass / stainless steel screws etc., complete as per architectural drawings. Prelaminated particle board with decorative lamination on both sides	25.00		sqm	
3 14. 53. 1B	Wall painting with plastic emulsion paint - Premium of approved brand and manufacture to give an even shade - One or more coats on old work	150.00		sqm	
	TOTAL				

Terms & Conditions:
   i)   The rates specified are firm and not subject to any variation.
   ii)   The work should be completed within 15 days.
   iii)   Payment will be made only after completion of the entire work.
   iv)   The material should be got approved before commencement of work.

CONTRACTOR   **EXECUTIVE ENGINEER**